

1-9

To: 1 070635  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,317-0000  
C NW SE, SEC. 32, T 20 S, R 23 W 45  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3372

Lease Name Stum Well # 1  
County Ness 143.33

Operator: Morrison-Dixon Oil Operations, Inc.  
Name & Address One Main Place, Suite 801  
Wichita, KS 67202

Well Total Depth 4410 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address Route 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 2:15 p.m. Day: 9 Month: 1 Year: 19 89

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-264-9632

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2227'  
Anhydrite 1440-70'  
1st plug at 1470' with 50 sx cement, 2nd plug at 700' with 80 sx cement,  
3rd plug at 290' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:15 p.m. Day: 9 Month: 1 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement,  
2nd plug at 700' with 80 sx cement,  
3rd plug at 290' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1989  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
Observe this plugging.

DATE 1-20-89  
INV. NO. 23744

Signed Dan Johnson  
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 12-29-88 month day year

API Number 15-135-23,317-0000

OPERATOR: License # 03372
Name Morrison-Dixon Oil Operations, Inc.
Address One Main Place- Suite 801
City/State/Zip Wichita, Kansas 67202
Contact Person Micheal W. Dixon
Phone (316)264-9632

C. NW. SE. Sec 32... Twp. 20. S. Rg 23... East
1980' Ft. from South Line of Section
1980' Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6039
Name L.D. Drilling, Inc.
City/State Great Bend, Kansas
Well Drilled For: Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 660' feet
County Ness
Lease Name Stum Well # 1
Ground surface elevation N.A. feet MSL
Domestic well within 330 feet yes X no
Municipal well within one mile yes X no
Depth to bottom of fresh water 75'
Depth to bottom of usable water 650'
Surface pipe by Alternate 1 2 X
Surface pipe planned to be set 250'
Conductor pipe required None
Projected Total Depth 4400' feet
Formation Mississippi

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 12-22-88 Signature of Operator or Agent Micheal W. Dixon Title Vice-President

For KCC Use:
Conductor Pipe Required 200' feet; Minimum Surface Pipe Required 200' feet per Alt. (2)
This Authorization Expires 6-22-89 Approved By LKM 12-22-88

RECEIVED STATE CORPORATION COMMISSION
EXPIRES DATE: 12-22-89

surf 260' / 150' sx all'd. Hual water

JAN 18 1989

C. NW. SE. Sec. 32., Twp. 20., S. Rg. 23... East
X West

CONSERVATION DIVISION
Wichita, Kansas

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep... B/An... or formation with... 50 SX... feet of... 60-40 RRZ
2nd plug @ ft. deep... B/Cheyenne... or formation with... 80 SX... feet of...
3rd plug @ ft. deep... 280'... or formation with... 40 SX... feet of...
4th plug @ ft. deep... 40-0'... or formation with... 10 SX... feet of...
5th plug @ ft. deep... RAT. hole... or formation with... 15 SX... feet of...
(b) Mousehole to surface minus 5 feet

Table with columns for well parameters: PUSHER (Greg Davidson), TD, SURFACE PIPE (8 5/8 @ 260), ANHYDRITE (1438-1472 ELEVATION), STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ 1470 FT. WI 50 SX, 2nd PLUG @ 700 FT. WI 80 SX, 3rd PLUG @ 290 FT. WI 40 SX, 4th PLUG @ 40 FT. WI 10 SX, RAT HOLE CIRCULATED WI 15 SX, MOUSE HOLE CIRCULATED WI SX, WATER WELL PLUGGED WI SX, CEMENT COMPANY, TECHNICIAN (RL). Includes handwritten notes like '60/40: 6 9/10'.