

1 030494

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,887-0000

C SE NE SE, SEC. 33, T 20 S, R 23

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5149

Lease Name Jedlicka Well # 1

Operator: Vincent Oil Corporation

County Ness 143.49  
(Mississippi)

Name & Address 125 North Market, Suite 1110

Well Total Depth 4415 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 1:00 am Day: 20 Month: August Year: 1985

Plugging proposal received from Tony Ernst

(company name) Wheatstate (phone) 316-672-7514  
Elevation 2234'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1430-1480'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 50' below the base of the Cheyenne with 80 sx cement

3rd plug at 30' below the base of the surface pipe  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement  
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)  
X

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:15 am Day: 20 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement, 2nd plug at 1200' with 80 sx  
cement, 3rd plug at 420' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug  
at 40' -- cement to surface with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

DATE AUG 28 1985

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 9843

AUG 28 1985

CONSERVATION DIVISION

FORM CP-2/3  
Rev. 01-84

P-20