

1 040009

11-17-87

API NUMBER 15- 135-23,186 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SW NE, SEC. 33, T 20 S, R 23 (W) X

3630 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Geckles Well # 1

Operator: Vincent Oil Corporation

County Ness 143.81

Name & Address 125 North Market, Suite 1110

Well Total Depth 4425 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 399

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 17 Month: 11 Year: 19 87

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

Elevation 2219'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1438-70'

1st plug at 1500' with 50 sx cement, 2nd plug at 850' with 80 sx cement,

3rd plug at 430' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 p.m. Day: 17 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement,

2nd plug at 850' with 80 sx cement,

3rd plug at 430' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORP. OR. REG. COMM. DIVISION

NOV 18 1987

OFFICE OF THE REGISTRAR
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 12-3-87

INV. NO. 19079

Signed Stephen J. Pfeifer (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 11 month 10 day 87 year
OPERATOR: License # 5004
Name Vincent Oil Corporation
Address 125 No. Market, Suite 1110
City State/Zip Wichita, Kansas 67202
Contact Person Julie K. Stout
Phone (316) 262-3573

API Number 15-135-23, 186-0000
C NW. SW. NE Sec. 33. Twp. 20. S. Rg. 23. East
3630 Ft. from South Line of Section
2310 Ft. from East Line of Section

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City State Wichita, Kansas 67202

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Ness
Lease Name Geckles Well # 1
Ground surface elevation applied for feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expt X Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 225
Depth to bottom of usable water 280
Surface pipe by Alternate 1 2 X
Surface pipe planned to be set 375
Conductor pipe required N/A
Projected Total Depth 4460 feet
Formation Mississippian

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq; plus eventually plugging hole to KCC specifications.
Date 11-3-87 Signature of Operator or Agent Richard A. Hiebsch Title Vice President

For KCC Use: Richard A. Hiebsch
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X
This Authorization Expires 5-5-88 Approved By R.A.H. 11-5-87

EFF. DATE: 11-10-87

SPUD 11-11-87
878-3154

C NW. SW. SE Sec. 33. Twp. 20. S. Rg. 23. East
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Pozmix details. Includes entries for 1st through 5th plugs and Rathole/Mousehole to surface minus 5 feet.

PUSHER Harold Maley
TD 4425 FORMATION MISS
SURFACE PIPE 8 3/8 @ 399
ANHYDRITE 1438 ELEVATION 2219
STARTING TIME & DATE 1:00 PM - 11-17-87
COMPLETION TIME & DATE 2:30 PM
1st PLUG @ 1500 FT. W/ 50 SX
2nd PLUG @ 850 FT. W/ 80 SX
3rd PLUG @ 430 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN

60/40 poz 679d

STATE OF KANSAS
NOV 18 1987
OFFICE OF THE DISTRICT ENGINEER
Wichita, Kansas