

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-165-21650-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Liboc, Inc. KCC LICENSE # 31741 <sup>8/97</sup>  
(owner/company name) (operator's)

ADDRESS 3300 S. Parker Rd., Suite 206 CITY Aurora

STATE Colorado ZIP CODE 80014 CONTACT PHONE # (303) 440-5767

LEASE Grabbe WELL# 1 SEC. 3 T. 16S R. 18 (East/West)

SW - NE - SW - SPOT LOCATION/QQQQ COUNTY Rush

1650 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

3630 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# 2-27-97

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1101' CEMENTED WITH 500 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3639' CEMENTED WITH 110 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 3560-68, CIBP @ 3558', Perfs: 3546-50'  
CIBP @ 3540'. Open perfs: 3512-14'

ELEVATION 1943'/1952' T.D. 3640' PBD 3540' ANHYDRITE DEPTH 1089'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off perfs at 3512'-14'. Dump 4sxs cement on top of sand.

Cut and pull 5-1/2" casing as deep as possible. Pump 40 sxs cement plug to base of 8-5/8" (1/2 in, 1/2 out). Set 5 sxs at surface. Cut off casing below plow level & weld on  
(If additional space is needed attach separate page) plate on dryhole marker if required.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? yes

If not explain why? Log submitted with ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Johnnie D. Odum PHONE# ( ) 303 440-5767

ADDRESS 3000 Pearl Street, Suite 210 City/State Boulder, CO 80301

PLUGGING CONTRACTOR DS&W Well Servicing Inc KCC LICENSE # 6901 <sup>6/97</sup>  
(company name) (contractor's)

ADDRESS Box 231, Claflin, KS 67525 PHONE # ( ) 316 587-3361

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) as soon as possible

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/21/97 AUTHORIZED OPERATOR/AGENT: Johnnie D. Odum (signature)



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 27, 1997

Liboc Inc  
3300 S Parket Rd Suite 206  
Aurora CO 80014

Grabbe #1  
API 15-165-21,650-0000  
1650 FSL 3630 FEL  
Sec. 03-16S-18W  
Rush County

Dear Johnnie D. Odum,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760