


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required AffidavitMail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202Locate well correctly on above
Section Plot

Rush County. Sec. 20 Twp. 16S Rge. 16W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
Approx. C S/2 NE NW
Lease Owner Chief Drilling Co., Inc.
Lease Name Caplinger "A" Well No. 1
Office Address 905 Century Plaza, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed December 22 1980
Application for plugging filed December 22 1980
Application for plugging approved December 22 1980
Plugging commenced December 22 1980
Plugging completed December 22 1980
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Schmidt
Producing formation Depth to top Bottom Total Depth of Well 3580
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1109	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plugged w/40 sx @ 840',
25 sx @ 300', Bridge to
hold Kelly @ 40' w/10 sx,
Filled rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Bill Lahar (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

515 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 80

My commission expires January 22, 1983

Betty M. Abbott

Notary Public.



15-165-20827-0000

DRILLERS LOG

December 30, 1980

#1 Caplinger "A"
Approx. C S/2 NE NW
Sec. 20-165-16W
Rush County, Kansas

OPERATOR: Chief Drilling Co., Inc.
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: December 15, 1980
COMPLETED: December 22, 1980

8 5/8" @ 1109' w/400 sx

0	922	Surface Clay	
922	1086	Red Bed	
1086	1125	Anhydrite	
1125	2434	Shale	
2434	3399	Lime & Shale	
3399	3580	Lime	
3580		RTD	D & A

We certify that the above and foregoing is a true and correct copy of the log on the #1 Caplinger "A" located in Rush County, Kansas.

B & B DRILLING, INC.


Bill Lahar

Subscribed and sworn to before me this 30th day of December, 1980.




Betty M. Abbott Notary Public

DEC 31 1980
RUSH COUNTY, KANSAS