


STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,750 

LEASE NAME Burns

WELL NUMBER 1

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 28 TWP. 20 SRGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed 5/22/93

Plugging Commenced 5/22/93

Plugging Completed 5/22/93

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Castle Resources, Inc.

ADDRESS 1200 E. 27th st., Suite C, Hays, KS 67601

PHONE#(913) -625-5155 OPERATORS LICENSE NO. 9860

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-22-93 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACQ-1 filed? No If not, is well loc. attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4440'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	201'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mud laden fluid 4440'-1640' 10 sks cement @ 40'

50 sks cement @ 1640' 10 sks in mousehole

50 sks cement @ 820' 15 sks in rathole

50 sks cement @ 240'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.


STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) 
Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1993


Glenda R. Tiffin, Notary Public

GLEND A. R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-96

Commission Expires: 2-6-96

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1993
CONSERVATION DIVISION
Wichita Form CP-4
Revised 05-88

15-135-23750-0000

EMPHASIS OIL OPERATIONS
A Division of N-B Company, Inc.
P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Castle Resources, Inc.
1200 E. 27th, Suite C
Hays, Kansas 67601

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Burns

WELL #1

LOCATION: C SE NW
Section 28-20S-24W
Ness County, Kansas

LOGGERS TOTAL DEPTH: 4442'

ROTARY TOTAL DEPTH: 4440'

COMMENCED: 5/15/93

CASING: 8-5/8" @ 201' w/120 sks cement

ELEVATION: 2325' K.B.

COMPLETED: 5/22/93

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	205'	Conglomerate	4285'
Anhydrite	1607'	Mississippi	4385'
Shale	1640'	R.T.D.	4440'
Lime & Shale	3500'		

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.




Kyle B. Branum

Subscribed and sworn to before me on May 24, 1993.

My commission expires: February 6, 1996.





Glenda R. Tiffin, Notary Public

RECEIVED
STATE OIL OPERATION COMMISSION

MAY 25 1993

OPERATION DIVISION
Ness County, Kansas