


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ness County. Sec. 29 Twp. 20S Rge. (E) 24 (W)  
Location as "NE/CNW%SW%" or footage from lines C/SE SE  
Lease Owner R. V. Lehner  
Lease Name Thompson Well No. 1  
Office Address P. O. Box 398, Ness City, Kansas 67560  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 19 19 67  
Application for plugging filed November 19 19 67  
Application for plugging approved November 19 19 67  
Plugging commenced November 19 19 67  
Plugging completed November 19 19 67  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4449 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	329.77'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 720' with 100 sacks of cement; plugged at 320' with 25 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 7:00 P. M. November 19, 1967.

RECEIVED  
NOV 21 1967

DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 67

My commission expires December 14, 1969

Elaine H. Taylor  
Elaine H. Taylor Notary Public.

D R I L L E R S   L O G

#1 THOMPSON

CASING RECORD: 329.77' of new 8-5/8" surface casing.	COMPANY: R. V. Lehner	DESCRIPTION: C/SE SE Section 29-20S-24W Ness County, Kansas
TOTAL DEPTH: 4449'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2354' DF
	COMMENCED: November 9, 1967	
	COMPLETED: November 19, 1967	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	109	Ran 329.77' of new 8-5/8" surface casing; set and cemented at 329.77' with 165 sacks sunset cement and 2% gel. Plug down at 8:45 P. M. November 9, 1967.
Shale	109	570	
Shale & Sand	570	1355	
Shale & Shells	1355	1602	
Shale & Lime	1602	3436	
Lime	3436	3552	
Lime & Shale	3552	4041	
Lime	4041	4350	
Lime & Chert	4350	4380	
Cherty Lime	4380	4449	

Total Depth 4449'

D. & A.

Plugged hole as follows: Plugged at 720' with 100 sacks of cement; plugged at 320' with 25 sacks of cement; plugged at 40' with 10 sacks of cement. Plug down at 7:00 P. M. November 19, 1967.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp  
Charles W. Steincamp, President

Subscribed and sworn to before me this 20th day of November, 1967.

Elaine H. Taylor  
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1969