

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-23,140-0000

LEASE NAME Otte

WELL NUMBER #1

330 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 28 TWP. 20 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-5-89

Plugging Completed 4-14-89

LEASE OPERATOR Ranken Energy Corp.

ADDRESS 3206 Teakwood Lane, Edmond, Okla 73013

PHONE# (316) 792-3664, OPERATORS LICENSE NO. 3447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which agent did you notify? Duane Rankin

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4475'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	736'	None
				5-1/2"	4474'	2,043.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 3990' and 5 sacks cement. Shot casing at 3600', 3000', 2800', 2500' & 2200' and 2000'. Pulled 67 joints of 5-1/2" casing. Howco plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 125 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 700 psi and shutin 500 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 20 1989

(Signature) James W. Rockhold

(Address) James W. Rockhold  
 Box 698, Great Bend, Ks. 67530

CONSERVATION DIVISION  
 WICHITA, KANSAS

WITNESSED AND SWORN TO before me this 19th day of April, 1989

Iona M. Leatherman  
 Notary Public

My Commission Expires \_\_\_\_\_

