

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 COLORADO DERRY BUILDING  
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-203-20,072-000

TYPE OR PRINT  
 PLEASE FILL OUT COMPLETELY  
 AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Dean

WELL NUMBER 1-4

SPOT LOCATION SE NW NE

SEC. 4 TWP. 19 RGE. 37 (E) OR (W)

COUNTY Wichita

DATE WELL COMPLETED 10-1-83

PLUGGING COMMENCED 9-29-83

PLUGGING COMPLETED 10-1-83

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P. O. Box 558, Garden City, KS 67846

PHONE # (316) 276-3693 OPERATORS LICENSE NO. 5293

CHARACTER OF WELL D & A  
 (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dist No. 1 Dodge City

IS ACC-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION ----- DEPTH TO TOP ----- BOTTOM ----- T.D. 5500'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE 8 5/8	PUT IN 463	PULLED OUT 0

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Plug thru drill pipe.  
Plug #1 3904' - 3790' w/ 30 sks of 60/40 Pozmix 2% gel & 3% CaCl dyed red. 7 7/8" bit upside down on top of plug.  
Plug #2 2300' - 2114' w/ 50 sks of 60/40 Pozmix 2% gel & 3% CaCl  
Plug #3 510' - 328' w/ 50 sks of 60/40 Pozmix 2% gel & 3% CaCl  
Plug #4 40' - Surface w/ 10 sks of 60/40 Pozmix 2% gel & 3% CaCl; Put 15 sks in rathole.  
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

Note: Radioactive neutron source left in well @ 3917' - 3940'.  
 NAME OF PLUGGING CONTRACTOR Halliburton LICENSE No. \_\_\_\_\_  
 ADDRESS Lamar, Colorado 81052

STATE OF Kansas COUNTY OF Finney, SS.

Millard L. Lindsay (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Millard Lindsay

(ADDRESS) P. O. Box 558, Garden City, Kansas 67846

SUBSCRIBED AND SWORN TO BEFORE ME THIS 14th DAY OF Oct, 1983

Betty J. Purdy  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: 6 Aug 1986

OCT 26 1983  
 10-26-83  
 NOTARY PUBLIC