

WELL PLUGGING RECORD

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

K.A.R. -82-3-117

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

API NUMBER 15-203-20,106-0000
 LEASE NAME HSR-Bauer
 WELL NUMBER 13-15

660 Ft. from S Section Line
660 Ft. from W Section Line

LEASE OPERATOR HS, Resources, Inc.
 ADDRESS 1999 Broadway, Suite 3600 Denver, CO 80202
 PHONE # (303) 296-3600 OPERATORS LICENSE NO. 31415
 Character of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 15 TWP. 19S RGE. 38W (E) or (W)
 COUNTY Wichita
 Date Well Completed July 8, 1994
 Plugging Commenced September 27, 1995
 Plugging Completed September 27, 1995

The plugging proposal was approved on July 19, 1995 (date)
 by David P. Williams, Production Supervisor (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? NA
 Producing Formation Winfield Depth to Top 2743' Bottom 2816' T.D. 3110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled Out	
Winfield	S. Wtr/Gas	Surface	403'	8-5/8"	9 jts	None	
Ft. Riley	S. Water	Surface	3100'	5-1/2"	71 jts	None	
Florence	S. Water						
Council Grove	S. Water						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pressure tested annulus to 500#, held for 15 minutes. Cementers pumped 300# of cotton seed hulls & 240 sxs cement down casing to plug the well. Steve Middleton with the State of Kansas was on location to witness the plugging. After the cement job, the well was pressured up to 500# and held for 15 minutes.

Name of Plugging Contractor Cementer's Energy, Inc. License No. 31718
 Address P.O. 1587, Scottsbluff, NE 69363-1587 (308) 632-8855
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HS Resources, Inc.

STATE OF Colorado COUNTY OF Denver ss.
Rick L. Parks, Operations Manager - Employee of Operator (Employee of Operator or Operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of
 the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Rick L. Parks*
 (Address) 1999 Broadway, Suite 3600 - Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 1995

Jo Ann Dubler
 Notary Public

My Commission Expires: September 10, 1997

