


15203-00031-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Wichita County, Sec. 26 Twp. 19S Rge. xxx38 (W)
Location as "NE/CNW&SW" or footage from lines Ctr NW NW
Lease Owner Texaco Inc.
Lease Name J. W. Roberts Well No. 1
Office Address 614 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-24-64 19
Application for plugging filed Attached 19
Application for plugging approved (Verbal) 8-31- 19 64
Plugging commenced 8-23- 19 64
Plugging completed 8-23- 19 64
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols - Morland, Kansas
Producing formation Dry Hole Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
Dry Hole				8-5/8"	290	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: 5354-1100 w/hvy mud,
1100-1000 w/30 sx cmt.,
1000-600 w/hvy mud,
600-500 w/30 sx cmt.,
500-300 w/hvy mud,
300-200 w/30 sx cmt.,
200-40 w/hvy mud,
40-5' w/10 sx cmt.

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1964
11-5-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
G. D. McColl (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. D. McColl

614 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of November, 19 64

A. E. Boyd

My commission expires 6-20-68

Notary Public.

WELL LOG

15.203.00031-0000

COMPANY **Texaco, Inc.**

SEC. 26 T. 19S R. 38W
LOC. NW NW

FARM **J. W. ROBERTS NO. One (1)**

RIS. NO. **2**

COUNTRY **Wichita Co., Ks.**
KANSAS

TOTAL DEPTH

5354'
7-29-64

COMP. **8-23-64**


QOMM.

SHOT OR TREATED

CONTRACTOR

Murfin Drilling Company

ISSUED



CASING

20

10
5/8" @ 289' w/250 sacks

ELEVATION

15

PRODUCTION

D&A

12

12

FIGURES INDICATE BOTTOM OF FORMATIONS

- 75 Clay, Surface Sand
- 290 Shale & Shells'
- 1070 Blue Shale
- 1095 Shale
- 1325 Shale
- 1710 Red Bed - Shale
- 1990 Salt
- 2061 Shale & Lime
- 2340 Red Bed & Shale
- 2355 Shale
- 2400 Anhydrite
- 2565 Shale & Stk Lime
- 2740 Lime & Shale
- 2975 Lime & Shale
- 3322 Lime
- 3404 Lime & Chert
- 3490 Lime
- 3777 Lime & Shale
- 3812 Chalky Lime
- 3835 Lime
- 3980 Lime & Shale
- 4076 Lime
- 5000 Lime & Shale
- 5038 Lime & Sand
- 5354 Lime
- 5354 RTD

RECEIVED
STATE CORPORATION COMMISSION

NOV 5 1964

CONSERVATION DIVISION
Wichita, Kansas

State of **KANSAS**

County of **SEDGWICK**

C. Robert Buford

of the

Murfin Drilling

Company

do hereby state that the above and foregoing is a true and correct copy of the log of the **J. W. Roberts #1** well.

MURFIN DRILLING COMPANY

By: *C. Robert Buford*
C. Robert Buford

Witness my hand and seal this **10th** day of **October** 19 **64**

Sandra J. Valzmea
Sandra J. Valzmea
NOTARY PUBLIC