


WELL PLUGGING RECORD

\*Get All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Scott County, Sec. 16 Twp. 18 Rge. 31W (E)      (W)  
Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner Donald C. Slawson  
Lease Name Reifschneider 'D' Well No. 1  
Office Address 200 Douglas Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed May 4 19 78  
Application for plugging filed May 4 19 78  
Application for plugging approved May 4 19 78  
Plugging commenced May 4 19 78  
Plugging completed May 4 19 78  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation      Depth to top      Bottom      Total Depth of Well 4675 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
	359'	surface	356'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

1st plug @ 1600' w/70 sx  
2nd plug @ 350 w/35 sx  
3rd plug @ 40' w/10 sx  
5 sx in rathole

5-26-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Co., Inc.  
Address 200 Douglas Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDCWICK, ss.  
R. J. Thatcher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Thatcher  
R. J. Thatcher, 200 Douglas Bldg., Wichita, KS  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of May, 19 78

My commission expires 10/7/79  
Janet R. Tunison Notary Public.



WELL LOG

OPERATOR: Donald C. Slawson  
 200 Douglas Building  
 Wichita, Kansas 67202

LEASE: #1 Reifschneider 'D'  
 C NE SW Sec. 16-18-31W  
 Scott County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
 200 Douglas Building  
 Wichita, Kansas 67202

COMMENCED: April 22, 1978

COMPLETED: May 4, 1978

CASING: Surface - 8 5/8" @ 356' w/275 sx 60/40 poz

MAY 26 1978

0 - 360	Surface hole
360 - 2262	Shale and shells
2262 - 2339	Anhydrite
2339 - 2795	Shale and shells
2795 - 2914	Shale
2914 - 4029	Shale and lime
4029 - 4075	Lime
4075 - 4142	Shale and lime
4142 - 4248	Lime
4248 - 4391	Shale and lime
4391 - 4415	Lime
4415 - 4521	Shale and lime
4521 - 4613	Lime
4613 - 4675	Shale and lime
4675	RTD

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK )

I, R. J. Thatcher, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log on the #1 Reifschneider 'D' test.

*R. J. Thatcher*  
 \_\_\_\_\_  
 R. J. Thatcher

Subscribed and sworn to before me this 24th day of May, 1978

*Janet R. Tunison*  
 \_\_\_\_\_  
 Janet R. Tunison, Notary Public

