

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171,20066-0000

LEASE NAME Lillian Long

WELL NUMBER 1-17

 Ft. from S Section 11

 Ft. from E Section 11

SEC. 17 TWP. 18 RGE. 31 (X) or ()

COUNTY Scott

Date Well Completed 11-74

Plugging Commenced 9-9-92

Plugging Completed 1:15 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Reserve Pipeline, Inc.

ADDRESS P.O. Box 1274, Liberal, Ks 67905

PHONE # (616) 624-6266 OPERATORS LICENSE NO. 08964

Character of Well Gas

(Oil Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-9-92 (date)

by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Depth to Top 2740 Bottom 2784 T.D. 2831

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	225	0
				4 1/2	2830	864

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each

Bottom plug: Sanded to 2690 & bailed 4 sx cement.

Top plug: Shot casing @ 1598 & spotted 80 sx cement (60/40 w/6% gel) through 4 1/2. Shot at 864 & pulled pipe to 300 ft & circulated 120 sx cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Reserve Pipeline, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 14 day of September, 19 92



Anna K. Burke
Notary Public