

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-171 20,130-0000
API NUMBER ~~XXXXXXXXXXXX~~

LEASE NAME Huling

WELL NUMBER 1-10

4020 Ft. from S Section Line

1340 Ft. from E Section Line

SEC. 10 TWP. 18 RGE. 31 ~~(E)~~ or (W)

COUNTY Scott

Date Well Completed 12-31-1976

Plugging Commenced 2-18-1991

Plugging Completed 2-21-1991

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Unico Inc.

ADDRESS Box 34, Farmington, NM 87499

PHONE# (303) 980-1277 OPERATORS LICENSE NO. _____

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-18-1991 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Krider Depth to Top 2756' Bottom 2760' T.D. 2910'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

2-25-91
FEB 25 1991

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	366'	0'
Production				4 1/2"	2909'	955'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
20 Sk. cement to 2400' - 50 Sk. cement @ 1600' Mud to 950'
50 Sk. cement 950' to 800' Mud 800' to 400' 50 Sk. cement 400' to 250'
Mud 250' to 40' - Bridge & 10 Sk. 40' to 3'
Cut off 8 5/8", 3' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Unico Inc.

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877



AND SWORN TO before me this 21st day of Feb., 1991

Sondra L. Eves
Notary Public

My Commission Expires: 12-6-92

STATE	KANSAS	2-3-29 HP	MAP NO.	S-T-R	10-18S-31W	WO
OPER	CAR-REN, INC.			SPOT	C NE/4	INIT
	300 W. DOUGLAS, WICHITA, KS			CO	SCOTT	WOE
WELL	1-10 HULING			ELEV	2928KB, 2923 GR	FIN
CONTR	GABBERT-JONES					
FIELD	EXT/HUGOTON NE(CHASE)					

IPF 118 MCFGPD, SIGW, CHASE(KRIDER)
 2756-60, API 15-171-20130 -0000
 SPUD 12-20-76, 8-5/8"@ 366 w/265, Geol-Charlie King
 & W. Walter Scott
 DST 1(HER-KRI) 2726-84, op10, si20, op105, si135,
 GTS/25" of 2nd op, ISIP 580, FP 53-53, 75-167,
 FSIP 569
 RTD 2910, log, 4½"@ 2909 w/150 ^{SG}
 Perf(KRI) 2756-60, SG, Nat, 4000 gal 15% A,
 IPF 118 MCFGPD, SIGW, CHASE(KRIDER) 2756-60
 COMPLETED 2-9-77 12-31-76

KB LOG TOPS:
 STONE CORRAL 2216 + 712
 B/STONE CORRAL 2276 + 652
 HERINGTON 2722 + 206
 KRIDER 2750 + 178
 WINFIELD 2798 + 130
 TOWANDA 2856 + 72
 RTD 2910 + 18
 TD IN CHASE

COMP ISSUED 2-21-77

CHASE - HUGOTON NE FIELD - EXTENSION

Correction: Field Was Wildcat, Initial Class Was WF

 Petroleum Information Corporation
 * Copyrighted 1977. Reproduction Prohibited

Made MAR 11 1977