

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20,418-0000

LEASE NAME Pfenninger "B"

WELL NUMBER I

4290' Ft. from S Section Line

2970' Ft. from E Section Line

SEC. 5 TWP. 18S RGE. 31 (E) or (W)

COUNTY SCOTT

Date Well Completed 12-28-90

Plugging Commenced 12-28-90 7:30 PM

Plugging Completed 12-28-90 8:00 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR SLAWSON EXPLORATION COMPANY, INC.

ADDRESS 104 S. BROADWAY, SUITE 200 Wichita, KS. 67202

PHONE# (316) 263-3201 OPERATORS LICENSE NO. 3988

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 28, 1990 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, Is well log attached? yes

Producing Formation ----- Depth to Top ----- Bottom ----- T.D. 2305'

Show depth and thickness of all water, oil and gas formations. 1-16-91

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	380	8 5/8"	380'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx. @ 2280', 80 sx. @ 1600', 50 sx. @ 410', 10 sx. @ 40', 15 sx. in rathole
Total 255 sx. 60/40 Pozmix, 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No.

Address Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Slawson Exploration Company, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis (Employee of Operator) or ~~(Operator)~~ of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis

L. D. Davis

(Address) Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1990



Bessie M. DeWerff
Notary Public

My Commission Expires: 5-20-93 Bessie M. DeWerff

DATE: 11-24-90

Expected Spud Date December 23 1990
month day year

SE NE NW Sec 5 Twp 18 S, Rg 31 East West

OPERATOR: License # 3938
Name: Slawson Exploration Co., Inc. ✓
Address: 104 South Broadway Suite 200
City/State/Zip: Wichita, Kansas 67202-4165
Contact Person: Robert B. Jenkins
Phone: (316) 263-3201

4290' feet from South line of Section ✓
2970' feet from East line of Section ✓
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6039 ✓
Name: L. D. Drilling, Inc.

County: Scott ✓
Lease Name: Pfenninger "B" Well #: 1 ✓
Field Name: Wildcat ✓

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary ✓
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OWWO ... Disposal Wildcat ... Cable
 Seismic; ... # of Holes

Is this a Prorated Field? ... yes no ✓
Target Formation(s): Mississippian ✓
Nearest lease or unit boundary: 330' ✓
Ground Surface Elevation: 2927' GR. (Seis) feet MSL ✓
Domestic well within 330 feet: ... yes no ✓
Municipal well within one mile: ... yes no ✓
Depth to bottom of fresh water: 150' ✓
Depth to bottom of usable water: 1650' ✓
Surface Pipe by Alternate: ... 1 2 ✓
Length of Surface Pipe Planned to be set: 365' ✓
Length of Conductor pipe required: None ✓
Projected Total Depth: 4650' ✓
Formation at Total Depth: Mississippian ✓
Water Source for Drilling Operations: Hauling ✓

If OWWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes no ✓
If yes, total depth location: _____

DWR Permit #: water well applied for ✓
Will Cores Be Taken?: ... yes no ✓
If yes, proposed zone: _____

AFFIDAVIT

200' Alt. II Req.

Exp. 5/19/91

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Eric Davidson INIT. RL
 SPUD DATE 12-26-90
 LENGTH SURFACE PLANNED 365'
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbbls. when done bbbls.
 RATHOLED AHEAD? Y N SIZE HOLE
 SURFACE PIPE 3 1/2" @ 380' CONDUCTOR
 ANHYDRITE T- 2267' B- 2687' ELEVATION
 TD 2305' FORMATION
 RAN PIPE @ SX DV TOOL @ SX ALT II DONE Y N
 Arbuckle Plug @ Ft. W/ SX
 Hug./Council @ Ft. W/ SX
 Anhydrite Base @ 2280' Ft. W/ 50' SX
1/2 Base Anhyd. @ 1600' Ft. W/ 80' SX
1/2, 1/2 Plug @ 800' Ft. W/ 50' SX
 Bottom Surface @ 410' Ft. W/ 50' SX
40' Plug @ 40' Ft. W/ 10' SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
 WATER WELL SX (Irr. Well Pond)
 Hauling
 TECHNICIAN R. L. DATE 12-28-90
 TYPE OF CEMENT 60/40
 STARTING TIME 6:00 (AM/PM) DATE 12-28-90
 COMPLETION TIME 8:00 (AM/PM) DATE 12-28-90
 CEMENT COMPANY Applied