

API NUMBER 15-171-20,393-0000

LEASE NAME Huseman

WELL NUMBER 2

4290 Ft. from S Section Line

4090 Ft. from E Section Line

SEC. 18 TWP. 18S RGE. 31W (E) or (W)

COUNTY Scott

Date Well Completed \_\_\_\_\_

Plugging Commenced 3:45 P.M. 8/25/89

Plugging Completed 11:45 P.M. 8/25/89

**CONFIDENTIAL**

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR BEREXCO INC.

ADDRESS 970 Fourth Financial Center

PHONE# (316) 267-9768 OPERATORS LICENSE NO. 5363

Character of Well Gas, Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Mr. Lacy

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	473'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged w/50 sks @2290', 80 sks @1700', 50 sks @500', 10 sks @40', 10 sks @MH, 15 sks @ RH. Cement was 60/40 Poz. 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Haliburton License No. \_\_\_\_\_

Address Box 428, Hays, KS 67601

STATE OF Kansas COUNTY OF Sedgwick, ss.

Evan C. Mayhew (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Evan C Mayhew  
(Address) 970 Fourth Financial Center  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of September, 1989

Laurie I. Noble  
Notary Public  
My Commission Expires: June 27, 1992



FORM MUST BE TYPED  
FORM C-1 12/88

State of Kansas  
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date August 10 1989 Approx. SE NW NW Sec 18 Twp 18 S, Rg 31 East  
month day year

OPERATOR: License # 5363  
Name: BEREXCO INC.  
Address: 970 Fourth Financial Center  
City/State/Zip: Wichita, KS 67202  
Contact Person: Evan Mayhew  
Phone: (316) 267-9768

CONTRACTOR: License #: 5147  
Name: BEREDCO INC.

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
X Gas ... Storage X Pool Ext. ... Air Rotary  
... OAWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OAWO: old well information as follows:  
Operator: .....  
Well Name: .....  
Comp. Date: ..... Old Total Depth .....

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location: .....

4290 feet from South line of Section  
4090 feet from East line of Section  
(Irregular Section) Locate well on Section Plat Below  
County: Scott  
Lease Name: Huseman Well #: 2  
Field Name: Beckley  
Is this a Prorated Field? ... yes X no  
Target Formation(s): LKC  
Nearest lease or unit boundary: 990'  
Ground Surface Elevation: 2960 feet MSL  
Domestic well within 330 feet: ... yes X no  
Municipal well within one mile: ... yes X no  
Depth to bottom of fresh water: 200'  
Depth to bottom of usable water: 1700'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 450'  
Length of Conductor pipe required: 0  
Projected Total Depth: 4600'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well ... farm pond X other  
DWR Permit #: .....  
Will Cores Be Taken?: ... yes X no  
If yes, proposed zone: .....

Spud 8-14-89 4708 ft

AFFIDAVIT

200' Alt. II Req.

PUSHER Howard Caine  
TD 4620 FORMATION Miss  
SURFACE PIPE 8 3/8 @ 470  
ANHYDRITE 2271-2273 ELEVATION  
STARTING TIME & DATE 8:00 P.M. 8-25-89  
COMPLETION TIME & DATE 11:45 P.M. 8-25-89  
1st PLUG @ 2270 FT. W/ 50 SX  
1700  
2nd PLUG @ 1908 FT. W/ 80 SX  
3rd PLUG @ 500 FT. W/ 50 SX  
4th PLUG @ 40 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ 10 SX  
WATER WELL PLUGGED W/ no w.w. SX  
CEMENT COMPANY Halliburton  
TECHNICIAN

TYPE OF CEMENT 60/40 per 62990

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 30 1989  
CONSERVATION DIVISION  
Wichita, Kansas

5280	1650
4950	1320
4620	980
4290	650
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field prorations orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.