

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-205220000

LEASE NAME WEISENBERGER

WELL NUMBER 1-18

2310 Ft. from 5 Section Line

1650 Ft. from 5 Section Line

SEC. 18 TWP. 18 RGE. 31 (E) or (W)

COUNTY SCOTT

Date Well Completed 3-04-98

Plugging Commenced 3-04-98

Plugging Completed 3-04-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3-11-98
15

LEASE OPERATOR CROSS BAR PETROLEUM, INC.

ADDRESS 7570 W. 21st St. Bldg. 1014 WICHITA, KANSAS 67205

PHONE (316) 721-4999 OPERATORS LICENSE NO. 4243

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 4, 1998 (date)

by STEVE DURRANT (KCC District Agent's Name).

Is ACO-1 filed? by operator if not, is well log attached?

Producing Formation na Depth to Top Bottom T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	311'	8 5/8"	311'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

2310' w/50 sx. 1500' w/80 sx., 750' w/40 sx. 330' w/50 sx. 40' w/10 sx. 15 sx. in rathole
Total: 245 sx. 60/40 Pozmix. 6% Gel 1/4# flo seal per sk. ALLIED CEMENTING SERVICE

Name of Plugging Contractor L. D. DRILLING, INC. License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CROSS BAR PETROLEUM, INC.

STATE OF KANSAS COUNTY OF BARTON, ss.

Bessie DeWerff (Employee of Operator) or (OPERATOR) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bessie DeWerff
Bessie DeWerff

(Address) R.R. 1 Box 183 B Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 98

Rashell Patten
Notary Public
Rashell Patten

My Commission Expires: 2-2-99

RASHELL PATTEN
M.A. 2-2-98

EFFECTIVE DATE: 10-14-97

State of Kansas

FORM MUST BE TYPED
FORM MUST BE SIGNED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 15-171-20,522-0000 ALL BLANKS MUST BE FILLED

SGA? Yes, X No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Spot NW NE SW Sec .. 18. Twp .18. S, Rg 31.. East
X West

Expected Spud Date .. 12 month 1 day 97.... year

OPERATOR: License #4243.....
Name: .CROSS BAR PETROLEUM, INC.
Address:7570 W. 21st St. Bldg 1014 Suite 8.....
City/State/Zip: ...WICHITA, KS 67205.....
Contact Person: ...MICHAEL BRYAN.....
Phone:316-721-4999.....

CONTRACTOR: License #: ... unknown.....
Name:advise on ACO 1.....

Well Drilled For: Well Class: Type Equipment:

- ..X Oil ... Enh Rec ... Infield X Mud Rotary
- .. Gas ... Storage ...X Pool Ext. .Air Rotary
- ... OWWO ... Disposal . Wildcat * ... Cable
- ... Seismic; ... # of Holes ... Other
- ... Other

If OWWO: old well information as follows:

Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes ..X. no

If yes, true vertical depth:.....

Bottom Hole Location.....

.....2310..... feet from South line of Section
1650..... feet from West line of Section
 IS SECTION X REGULAR _____ IRREGULAR?
 (NOTE: Locate well on the Section Plat on Reverse Side)
 County: Scott

Lease Name: Weisenberger Well 1-18

Field Name: Beckley.....

Is this a Prorated/Spaced Field? yes ..X no

Target Formation(s):MISSISSIPPIAN

Nearest lease or unit boundary:330'

Ground Surface Elevation: EST.2959 feet MSL

Water well within one-quarter mile: ... yes ..X. no

Public water supply well within one mile: yes ..X. no

Depth to bottom of fresh water:180'

Depth to bottom of usable water:1220' 1500.....

Surface Pipe by Alternate: ... 1 ..X. 2

Length of Surface Pipe Planned to be set:300'.....

Length of Conductor pipe required:N/A.....

Projected Total Depth:4650.....

Formation at Total Depth:MISSISSIPPIAN

Water Source for Drilling Operations:
 . . well farm pond ..X. other

Will Cores Be Taken? yes ..X. no

If yes, proposed zone:

200' Alt. II Req.

Exp. 4/9/98

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Norm/LD Daly

SPUD DATE 2-17-98 INIT. SR

LENGTH SURFACE PLANNED 300' of 8 5/8"

RESERVE PIT STATUS- REMOVE FLUID _____ LINED _____
 after salt sect. _____ bbls. _____ when done bbls.

RATHOLED AHEAD? Y _____ N _____ SIZE HOLE _____
 SURFACE PIPE 3 1/2" @ 313 CONDUCTOR _____
 ANHYDRITE T- 2265 B- 2305 ELEVATION _____

TD 4630 FORMATION _____

RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
 _____ SX _____ Y _____ N _____

Arbuckle Plug @ _____ Ft. W/ _____ SX _____

Hug./Council @ _____ Ft. W/ _____ SX _____

Anhydrite Base @ 2310 Ft. W/ 50 SX _____

1/2 Base Anyh. @ 1500 Ft. W/ 80 SX _____

1/2, 1/2 Plug @ 750 Ft. W/ 40 SX _____

Bottom Surface @ 330 Ft. W/ 50 SX _____

40' Plug @ 40 Ft. W/ 10 SX _____

RAT HOLE CIRC/W 15 SX MOUSE HOLE ~~15~~ SX _____

WATER WELL _____ SX (Irr. Well _____ Fond _____)
 _____ Hauling _____

TECHNICIAN SM DATE 2-22-98

TYPE OF CEMENT 62K40670 141-1094

STARTING TIME 2:30 (AM/PM) DATE 3-4-98

COMPLETION TIME 6:30 (AM/PM) DATE 3-4-98

CEMENT COMPANY Attland