

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL RECORD

STAFFORD

County, Sec. **16** Twp. **25S** Rge. **15W** (E) (W)

Location as "NE/CNW3SW" or footage from lines. **C NE SE**

Lease Owner **N. C. R. A.**

Lease Name **FEIDEL** Well No. **1**

Office Address **Rule Building, Wichita 2, Kansas**

Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**

Date well completed **June 27, 1961**

Application for plugging filed **June 27, 1961**

Application for plugging approved **June 27, 1961**

Plugging commenced **June 27, 1961**


Plugging completed **June 27, 1961**

Reason for abandonment of well or production formation **Dry Hole**

19

When plugging of well began, had you or your agents before plugging was commenced?

Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well **Frank Broadfoot, St. John, Kansas**

Producing formation _____ Depth to top _____ Feet Total Depth of Well **4310** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shale	Surface Csg.	-0-	265'	8-5/8"	265'	None

Describe in detail the manner in which the well was plugged, including when the cement fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the size of the plug and the depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled hole with heavy mud from 4310' to 240'. Bridged using 1/4 sk. hulls, Halliburton plug, 20 sx. cement through drill pipe. Filled hole with mud up to 35'. Bridge using 1/2 sk. hulls, Halliburton plug, 10 sx. cement to cellar zero.

Job Completed: 4:45 p.m. 6-27-61.

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, see Part A of this report)

Name of Plugging Contractor **Sierra Petroleum Co., Inc.**

Address **208 Petroleum Building, Wichita, Kansas**

STATE OF **KANSAS** COUNTY OF **RUSSELL** SS.

C. T. HONAKER, SUPERINTENDENT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, circumstances, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. T. Honaker* **C. T. HONAKER, DRIG. SUPT.**

BOX 232, RUSSELL, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this **28th** day of **June**, 19**61**

Geroy Drey
Notary Public.

My commission expires **10-17-63**

INVOICED

DATE **6/29/61**

INV. NO. **3356-w**

15-185-1012-0000

N. C. R. A. - Operator

SIERRA PETROLEUM CO., INC. - Contractor

WELDER #1
C NE SE
Sec. 16-25S-15W
Stafford County, Kansas

T. D.: 4310'
Elev.: 2033' K.B.

Commenced: 6-15-61
Completed: 6-27-61

Casing:

Cement:

8-5/8" Set at 265'

with 225 sx. cement

FORMATION

DEPTH

Sand	170
Shale	330
Red Bed	970
Anhydrite	983
Shale & Shells	1825
Shale & Lime	3480
Lime	3635
Lime & Shale	3815
Lime	4132
Lime & Shale	4179
Lime, Shale & Chert	4245
Mississippi	4310

TOPS:

Heebner	3639
Toronto	3659
Douglas	3677
Brown Lime	3784
Lansing Kansas City	3801
Base of Kansas City	4078
Conglomerate	4204
Mississippi	4226

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true
and correct to the best of my knowledge.

C.T. Honsaker

Subscribed and sworn to before me this 28th day of June, 1961.

Leroy Dick
Notary Public

My commission expires: 10-17-63

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1961
CONSERVATION DIVISION
Wichita, Kansas