


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rush County. Sec. 2 Twp. 16S Rge. 16 (EXX) (W) West

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW&" or footage from lines. SE SE SE
Lease Owner El Dorado Refining Co.
Lease Name Pospishel Well No. 1
Office Address 306 Koch Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-27-53 19
Application for plugging filed 10-30-53 19
Application for plugging approved 19
Plugging commenced 10-27-53 19
Plugging completed 10-27-53 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud from T.D. to 300'. Set plug and cemented with 1/2 sack Hulls and 20 sacks cement; Filled hole with extra heavy drilling mud from 300' to 40' with 1/2 sack Hulls and 10 sacks Cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company
Address 1005 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Prime Drilling Company (Contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1005 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October, 19 53

My commission expires Oct. 14, 1957
[Signature] Notary Public.

24-7966-5 3-53-20M
PLUGGING
FILE REC 2 16 16 W
PAGE 139 LINE 17

ROTARY DRILLING LOG

OPERATOR: El Dorado Refining Company
 #1 Pospishel
 SE SE SE Sec. 2-16S-16W
 Rush County, Kansas

CONTRACTOR: Prime Drilling Co.
 COMM: 10-14-53
 COMP: 10-27-53

FORMATION

REMARKS

Surface Clay & Rock	40'	Ran 121' 4 jts. 13-3/8
Shale	137'	48# Casing set @ 119'
Shale & Shells	405'	Cemented with 150 & 3 sks.
Sand	660'	cc.
Red Bed & Shale	720'	
Red Bed, Shale & Iron	800'	
Red Bed	875'	
Red Bed & Shale	1027'	
Anhydrite	1030'	
Red Bed & Shale	1217'	
Shale & Sand	1475'	
Shale & Shells	1760'	
Shale & Lime	1915'	
Lime	3100'	
Lime & Shale	3540'	
Lime	3585'	
Total Depth	3585'	

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

BY R. R. McNicol
 R. R. McNicol

FILED 10-27-53 16 16W
 139 17