


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rush County, Sec. 8 Twp. 16S Rge. 16W (E) (W)  
Location as "NE/CNW&SWK" or footage from lines NW SW NE  
Lease Owner Rains & Williamson Oil Co., Inc.  
Lease Name Weber Well No. 1  
Office Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-25-73 19  
Application for plugging filed 7-25-73 19  
Application for plugging approved 7-25-73 19  
Plugging commenced 7-25-73 19  
Plugging completed 7-25-73 19

Reason for abandonment of well or producing formation  
commercial quantities of oil not found

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3510' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1049'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug at 400' w/ 25 sx.  
Plug at 40' w/ 10 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.  
Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK  
Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_  
435 Page Court, 220 W. Douglas, Wichita, Kansas 67202  
(Address)



Subscribed and sworn to before me this 8th day of August, 1973  
October 4, 1975  
Juanita M. Green Notary Public

15-165-20471-0000  
WELL LOG

COMPANY Rains & Williamson Oil Co., Inc.

SEC. 8 T-16S R-16W  
LOC. NW SW NE

FARM Weber NO. 1


RIG. NO. 4

TOTAL DEPTH 3510

COMM. 7-16-73

COMP. 7-25-73

COUNTY Rush  
KANSAS



CONTRACTOR Rains & Williamson Oil Co., Inc.

CASINO

20 10  
15 10  
12 6  
13 5

8 5/8" @ 1049' w/ 250 sx. 50/50 pos, 2% gel, 2% cc;  
& 200 sx. 60/40 pos, 2% gel, 2% cc.

ELEVATION 1928 KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock	45
Shale and Sand	370
Shale, Sand and Red Bed	900
Shale	1040
Anhydrite	1080
Shale	1745
Shale and Lime	2705
Lime and Shale	2920
Lime	3490
Arbuckle	3510
<u>Rotary Total Depth</u>	<u>3510</u>

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS }  
County of SEDGWICK } ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc. ~~XXXXXX~~

upon oath state that the above and foregoing is a true and correct copy of the log of the Weber #1 well.

Wilson Rains  
WILSON RAINS

Subscribed and sworn to before me this 8th day of August 19 73

My Commission Expires: October 4, 1975

Juanita M. Green  
NOTARY PUBLIC  
Juanita M. Green

