

15.165-01895.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rush

County. Sec. Twp. Rge. (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines

Lease Owner **Carl Lebsack**

Lease Name **ROY-Fred-Brack** **AUG. K.C.** Well No. **1**

Office Address **Hays, Kansas**

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced **12-7-50** 19

Plugging completed **12-12-50** 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Petty**

Producing formation **Arbuckle** Depth to top **3528** Bottom Total Depth of Well **3540** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1040'	0
				5-1/2"	3534'	3046'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 3540' to 3525' and ran 5 sacks cement. Mudded hole from 3475' to 260', set 10' rock bridge and ran 15 sacks cement. Mudded hole to 30' and ran 10 sacks cement on top. Well completed.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to **Carl Lebsack**
Address **Chase, Kansas**

STATE OF **Kansas**, COUNTY OF **Ellis**, ss.

Olton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) **Carl Lebsack**

SUBSCRIBED AND SWORN TO before me this **23rd** day of **December**, 19 **50**

(Address)
Delmer L. Shney
Notary Public.

My commission expires **July 14, 1957**

PLUGGING
FILE SEC-15T 16R 16W
BOOK PAGE 49 INT 31

Company: Carl Lebsack et al
 Contractor: Glenn R. Nye Drilling Company
 Commenced: October 8, 1950
 Completed: October 22, 1950

Farm: Brack No. 1 Well
 Location: NE SE SE Sec. 15-16-16
 Rush County, Kansas
 Casing Record: 8 5/8" set at 1051'
 5 1/2" set at 3534'

(Figures below indicate bottoms)

surface clay	40
sand & shale	90
sand & shale	375
shale & iron	385
iron & shale streaks	410
shale	450
shale	490
Dotoka sand	645
red bed	675
iron pyrite	685
iron pyrite	697
shale & red bed	730
iron pyrite & shale	755
iron pyrite	780
shale & shells	830
shale & shells	1035
shale & shells	1040
anhydrite	1052
anhydrite	1060
anhydrite	1075
shale & shells	1390
shale & shells	1420
salt & shale	1505
salt	1560
salt & shale	1650
shale & shells	1770
shale & lime st.	1905
lime	2025
lime	2045
red shale	2105
lime & shale	2135
lime	2200
lime & shale	2260
lime & shale	2300
lime & shale	2340
shale & lime	2435
shale & lime	2575
shale & lime	2590
shale	2708
shale & lime	2812
shale & lime	2909
lime & shale	3000
lime & shale	3048
lime & shale	3104
lime & shale	3147
lime & shale	3192
lime & shale	3208
lime	3248
lime	3298
lime - hard	3334
lime	3375
lime	3420
lime	3456
lime	3495
lime & shale	3530
lime & shale	3534

top Arbuckle 3529
 T. D.

RECEIVED
 STATE CORPORATIONS COMMISSION
 DEC 26 1950
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

State of Kansas) **PLUGGING** Glenn R. Nye Drilling Company
 Ellis County) FILE SEC 15 T 16 R 16
 By Glenn R. Nye
 BOOK PAGE 49 LINE 31

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 1 day of Nov, 1950.

My Commission Expires, May 9, 1953
John L. Weiss
 Notary Public

Carl Lebsack - ^{Roy} Fred Brack #1
and co
 Day Work and Well Abandment

DATE	LEBSACK TIME	REMARKS
12-7-50	2	Checked hole, hole clear.
12-8-50	10	Rocked hole from 3540' to 3525' and ran 5 sacks cement. Cleaned cellar and took tension on pipe. Had 19" tension at 84,000#.
12-9-50	8	Shot pie at 3300', 3220', 3190', 3160' and worked tension to 24".
12-10-50	10	Hooked up Circulating pump but pipe would not take fluid at 1250#. Shot pipe at 3130', 3060', 3000'. Pipe took fluid at 900#, broke to 400#. Displaced 50 barrels oil with water. Tension still 24" at 84,000#. Pumped plug to 2985'.
12-11-50	5	Worked pipe loose at 3000', leveled up and pulled 40 joints.
12-12-50	7	Pulled 57 joints, mudddd hole from 3475' to 260' and set 10' rock bridge. Ran 15 sacks cement, mudded to 30' and ran 10 sacks cement on top.

Well Completed

Well was plugged as per plugging instructions from State Pluggger.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 26 1950

REGISTRATION DIVISION
 Wichita, Kansas