

15-047-20149-0000

STATE CORPORATION COMMISSION

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

AUG 22 1985

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER comp date 8/13/74 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Sterling Drilling Co. OPERATORS LICENSE NO. 5142

ADDRESS Box 129, Sterling, Ks. 67579 PHONE # (316) 278-2131

LEASE (FARM) Mitchell #1 WELL NO. _____ WELL LOCATION S/2 S/2 NW/4 COUNTY Edwards

SEC. 5 TWP. 24s RGE. 16w (M) or (W) TOTAL DEPTH 4290' PLUG BACK TD _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 322' CEMENTED WITH 275 SACKS

CASING SIZE 4 1/2" SET AT 4288' CEMENTED WITH 375 SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

Will plug according to rules & regulations of State of Kansas.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Olin Kelso PHONE # (316) 278-2131

ADDRESS Sterling, Ks. 67579

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, Ks. 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: August 19, 1985

①

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- MITCHELL #1
Located: S/2 S/2 NW, Section 5-24S-16W, Edwards County, Kansas

OWNER: Kansas-Nebraska Natural Gas Company, Inc., Voyager Petroleum, Inc.
and Sterling Drilling Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 31, 1974
COMPLETED: August 13, 1974

TOTAL DEPTH: 4290'

LOG

CASING RECORD

0 - 100	Sand and Surface Clay	Ran 8 joints 28#, 8 5/8" surface. Set at 322' K.B. Cemented with 275 sacks 60/40 Pozmix, 3% cc, 2% gel. Plug down at 9:30 PM, 7-31-74.
100 - 330	Sand and Shale	
330 - 1130	Shale	
1120 - 1860	Shale, Salt, Lime	
1860 - 2145	Lime	
2145 - 2245	Lime, Shale	
2245 - 2435	Lime	
2435 - 3110	Lime and Shale	
3110 - 3215	Lime	
3215 - 3300	Lime and Shale	
3300 - 3665	Lime	
3665 - 3748	Shale	
3748 - 4030	Lime	
4030 - 4100	Lime and Shale	
4100 - 4290	Lime	

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1975

CONSERVATION DIVISION
Wichita, Kansas

Ran 4308' 4 1/2" casing, set at 4288', 1 ft. off bottom, 5 centralizers. Plug down at 2:00 AM, 8-13-74. Set with 200 sacks Halliburton Light, 10% gilsonite per sack; 175 sacks 50/50 Pozmix, with 2% gel, 18% salt, 3/4 of 1% CRF₂, plus 10% gilsonite per sack.



MARK CARLIN
MICHAEL LENNEN
DEBRA LEE WRIGHT
DORIS R. HENLEY
DITH A. MCCONNELL
IAN J. MOLINE

Governor
Chairman
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

NOV 22 1985

EXPIRES

August 22, 1985

WELL PLUGGING NOTICE

Mitchell #1
S/2 S/2 NW/4
Sec. 5-24S-16W
Edwards County

Sterling Drilling Co.
Box 129
Sterling, KS 67579

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to
DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760
five days prior to plugging the well (KAR-82-3-113).