

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-203-20,110-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR WOOLSEY PETROLEUM CORPORATION KCC LICENSE # 5506  
(owner/company name) (operator's)  
ADDRESS 107 N. MARKET, STE 600 CITY WICHITA

STATE KANSAS ZIP CODE 67202-1807 CONTACT PHONE # (316)267-4379

LEASE W. R. WELLS WELL# 1 SEC. 7 T. 20S R. 35 (East/West)

C NW - NW - SW - SPOT LOCATION/QQQQ COUNTY WICHITA

2310 FSL FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FWL FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  DRA  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE n/a SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 211.48' CEMENTED WITH 60-40 posmix-160 SACKS

PRODUCTION CASING SIZE n/a SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: n/a

ELEVATION 3173'/3178' T.D. 5613' PETD \_\_\_\_\_ ANHYDRITE DEPTH 2283'-2299'  
(G.L./R.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2300' w/50 sx; 2nd plug @ 1250' w/80 sx; 3rd plug @ 720' w/40 sx; 4th plug @ 220' w/40 sx; 5th plug @ 40' w/10 sx; rathole 15 sx.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

GARY FISHER

PHONE# (913) 743-5654

ADDRESS P.O. BOX 673 CITY/STATE SCOTT CITY, KS 67871-0673

PLUGGING CONTRACTOR ABERCROMBIE RTD, INC. KCC LICENSE # 30684  
(company name) (contractor's)

ADDRESS 150 N. MAIN, STE 801, WICHITA, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (if known?) COMPLETE AT 10:00 P.M. 6-25-94

PAYMENT OF THE PLUGGING FEE (K.S.A. 52-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 08/09/94 AUTHORIZED OPERATOR/AGENT: I. Wayne Woolsey

(signature)  
I. Wayne Woolsey, President