

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-171,20,381-0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Luff Exploration Company OPERATOR'S LICENSE NO. 7185

ADDRESS 1580 Lincoln St., Suite 850, Denver, CO 80203 PHONE # (303) 861-2468

LEASE (FARM) Malone WELL NO. A-11 WELL LOCATION NE NE NE COUNTY Scott
SEC. 11 TWP. 18S RGE. 31 ~~(R) (W)~~ TOTAL DEPTH 4599' PLUG BACK TD _____

Check One:

OIL WELL ___ GAS WELL ___ D & A X SWD or INJ WELL ___ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 308.12' CEMENTED WITH 175 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 2270'-50 sx. 2nd plug at 1500'-80 sx. 3rd plug at 340'-40 sx. 4th plug at 40'-10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 7:15 p.m. on 9-02-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harvey Moore PHONE # (316) 995-4955

ADDRESS Box 163, Belpre, KS 67519

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wianton
(Operator or Agent)

DATE: 9-21-89

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1989
9-22-89
CONSERVATION DIVISION
Wichita, Kansas