

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-00057-00-00  
Spot: CNWNE Sec/Twnshp/Rge: 4-20S-24W  
660 feet from N Section Line, 410 feet from W Section Line  
Lease/Unit Name: LUNDY-HAIR Well Number: 1  
County: NESS Total Vertical Depth: 4473 feet  
Operator License No.: 31627 Conductor Pipe: Size \_\_\_\_\_ feet: 16/45.37  
Op Name: WHITETAIL CRUDE, INC Surface Casing: Size 8.625 feet: 270  
Address: N HWY 283 PO BOX 544 Production: Size 5.5 feet: 4470 WITH 150 SX CMT  
NESS CITY, KS 67560 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2002 4:45 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 3850' & 4 SX CMT. PUMP 50 SX CMT & 100# HULLS TO 1800'. SHOOT OFF PIPE AND PUMP 40 SX CMT. TOP OFF WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/29/2002 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4424'. PERFS AT 4401-02 & 4410-14'. FOUND HOLE AT 3400'. PACKER STUCK IN HOLE. COULD NOT GET OUT. PACKER IN HOLE AT 3900'. SANDED TO 3850' WITH 4 SX CMT. PUMPED 50 SX CMT & 100# HULLS TO 1800'. SDON. 10/29/02: SHOT PIPE AT 720'. DID NOT COME LOOSE. PUMPED 80 SX CMT. SHOT PIPE AT 462'. CAME LOOSE. PULLED TO 300' & PUMPED 40 SX CMT. PULLED REMAINING CASING. TOPPED OFF WITH 10 SX CMT. HOLE STAYED FULL.

RECEIVED  
11-7-02  
NOV 07 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 462' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Michael Maier  
(TECHNICIAN)

INVOICED

DATE

11-7-02

NOV. NO.

2003060789

FORM 0123