

To: 1 030565
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759
Operator: Mack Energy Company
Name & Address P. O. Box 400
Duncan, OK 43534

API NUMBER 15- 135-22,939-0000
C NW SE SE, SEC. 19, T 20 S, R 24 WXB
990 feet from S section line
990 feet from E section line
Lease Name Copeland Well # 2
County Ness
Well Total Depth 4500 Mississippi 46 25 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 495

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x
Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Co., Inc. License Number 5146
Address 435 Page Court, 220 West Douglas, Wichita, KS 67202
Company to plug at: Hour: 11:00 pm Day: 30 Month: October Year: 19 85
Plugging proposal received from Bob Caulk

(company name) Rains & Williamson (phone) 316-265-9686
Elevation 2363
were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1621-33'

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge
- 3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 5th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 12:01 am Day: 31 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1665' with 50 sx cement, 2nd plug at 525' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 4 1985
INV. NO. 10884 / 10-31

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1985

Signed Steve Durrant
(TECHNICIAN)