

1 100060

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,808-0000

SW NW SW, SEC. 20, T. 20 S, R. 24 W EX

1650 feet from WYS section line

4950 feet from WWE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759

Lease Name Lehner Well # 1

Operator: Mack Energy Co.

County Ness

Name & Address P. O. Box 400

Well Total Depth 4500 146.25 feet (Mississippi)

Duncan, OK 73534

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 535 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Co., Inc. License Number 5146

Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 16 Month: May Year: 19 85

Plugging proposal received from Bob Klotz

(company name) Rains & Williamson (phone) 316-739-8721

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1603-1645'
Elevation 2337'

1st plug at 1640' with 50 sx cement

2nd plug at 1120' with 50 sx cement

3rd plug at 555' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement.

Plugging Proposal Received by [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:00 am Day: 16 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1640' with 50 sx cement, 2nd plug at 1120' with 50
sx cement, 3rd plug at 555' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by BJ-Titan
(if additional description is necessary, use BACK of this form) Wichita, Kansas

CONSERVATION DIVISION

I (did not) observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE 5-21-85
INV. NO. 8211 5-16