

To: 1 030640
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,660-00-01
NE SE SW, SEC. 34, T 20 S, R 24 W
990 feet from S section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9860
Operator: Castle Resource
Name & Address: R. R. 1 Stonewood Estates
Slot 8, Hays, KS 67601

2970 feet from E section line
Lease Name Humberg Ranch Well # 1
County Ness 35.00
Well Total Depth 876 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A OWWO

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling, Inc. License Number 4083
Address P. O. Box 126, Hays, KS 67601

Company to plug at: Hour: 8:00 am Day: 4 Month: January Year: 19 86

Plugging proposal received from Frank Taggart
(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at the base of the Anhydrite with 50 sx cement
2nd plug 50' below the base of the Cheyenne with 80 sx cement
3rd plug at 360' with 40 sx cement
solid bridge
4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:15 am Day: 4 Month: January Year: 19 86

ACTUAL PLUGGING REPORT Bit went out of the hole at 675' when attempting wash down.

1st plug at 876' with 50 sx cement, 2nd plug at 360' with 40 sx cement, 3rd & 4th plugs -
solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986
INV. NO. 12027

STATE CORPORATION COMMISSION
Signed Steve Durrant
(TECHNICIAN)

JAN 13 1986
FEB 5 1986
MAR 27 1986
CONSERVATION DIVISION