

1 050207

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-21,826-6000  
NE of C SW SW SEC. 34, T 20 S, R 24 W/E  
150' NE of C SW SW  
feet from N/S section line  
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Humburg Ranch Well # 2

Operator: Rains & Williamson Oil Co., Inc.  
Name & Address 435 Page Court, 220 W. Douglas  
Wichita, KS 67202

County Ness  
Well Total Depth 4460 144.95 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 486

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: Noon Day: 1 Month: May Year: 19 84

Plugging proposal received from Jim Ray

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2 set at 4459 Open Hole

1st plug sanded back to 4400 and dumped 4 sx cement on top of sand

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel and released  
8 5/8" rubber plug and pumped an additional 125 sx cement

Maximum pressure 1500 psi Shut in pressure 500 psi

Plugging Proposal Received by Richard W. Lacy  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 1 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4459' Open Hole

1st plug sanded back to 4400' and dumped 4 sx cement on top of sand, 2nd plug squeezed  
well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel and released 8 5/8" rubber plug  
and pumped an additional 125 sx cement.

Maximum pressure 1500 psi Shut in pressure 500 psi

Remarks: They recovered 2400' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3%cc by Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-14-84

INV. NO. 1478

RECEIVED

MAY 07 1984

CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lacy  
(TECHNICIAN)