

To: 1 070662
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SW SW, SEC. 28, T 20 S, R 24 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-14
API NUMBER 15- 135-23,140-0000
330 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3447
Operator: Ranken Energy Corporation
Name & Address: 3206 Teakwood Lane
Edmond, OK 73013

Lease Name Otte Well # 1
County Ness 145.44
Well Total Depth 4475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 736

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 14 Month: 4 Year: 1989

Plugging proposal received from Deacon Pulley
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4474' PBD 3976' Perfs at 4026-30' Anhydrite 1609'

1st plug pump 5 sx cement on CIBP at 3976',

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 14 Month: 4 Year: 1989

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3976', sand to 3926', dump 5 sx cement on top,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, **RECEIVED** hulls, released
STATE CORPORATION COMMISSION

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 500 psi. APR 20 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2000' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (and/or ~~XXXXXXXX~~) observe this plugging.

Signed Don Jordan
(TECHNICIAN)

DATE 4-27-89

INV. NO. 24509