

V1 051068

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita, KS 67202

9-29

API NUMBER 15-203-20,033-0001

PLUGGING SECTION App. NW SW SE, SEC. 9, T 19 S, R 38 W/EX

1250 feet from S section line
2565 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31415

Operator: HS Resources, Inc.
Name:
Address 1999 Broadway, Ste. 3600
Denver, CO 80202

Lease Name HSR-Myers Well # 15-9

County Wichita 101.82

Well Total Depth 3133 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Cementers, Inc. License Number

Address 1701 1st Ave., Greeley, CO 80631

Company to plug at: Hour: 9 a.m. Day: 29 Month: 9 Year: 1995

Plugging proposal received from Jim Parks

(company name) HS Resources Inc. (phone) 303-296-3600

work: 4 1/2" at 3133' w/180 sx cement, PBTD 2914', Perfs at 2907-17, 2818-24, 2769, 2737'

1st plug pump 200 lbs. hulls and 40 sx cement on bottom, Perforate at 1400'

2nd plug pump down 4 1/2" with 40 sx cement,

3rd plug pump 200 sx cement down 8 5/8" X 4 1/2" annulus.

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1995

10-9-95
CONSERVATION DIVISION
Richard Lacey
Wichita, Kansas

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 29 Month: 9 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 40 sx cement, displaced to 2500',

2nd plug perforated at 1400', pumped down 4 1/2" with 40 sx cement, pressured to 1750'

3rd plug pumped 200 sx cement down the 8 5/8" X 4 1/2" annulus.

Remarks: Used Class H 6% gel cement by Cementers Inc. No casing recovery.

(if additional description is necessary, use BACK of this form.)

INVOICED

(200) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 10-9-95

INV. NO. 43705

9-29