

V1090587

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SEP 27 1995

API NUMBER 15- 203-20,106 -0000

C SW SW, SEC. 15, T 19 S, R 38 W/E

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31415

Lease Name HSR-Bauer Well # 13-15

Operator: HS Resources, Inc.

County Wichita 101.08

Name & Address 1999 Broadway, Ste. 3600

Well Total Depth 3110 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Cementers, Inc. License Number _____

Address 1701 1st Ave., Greeley, CO 80631

Company to plug at: Hour: 12:30 p.m. Day: 27 Month: 9 Year: 1995

Plugging proposal received from Chad Parks

(company name) HS Resources, Inc. (phone) 303-296-3600

Work: 5 1/2" at 3100' w/565 sx cement, PBD 3081', Perfs at 2804-10'

1st plug pump down 5 1/2" casing with 3 sx hulls and 245 sx cement.

Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 27 Month: 9 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 245 sx cement down 5 1/2" casing.

Maximum pressure 500 psi and shut in 500 psi.

Backside pressured to 500 psi.

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 1995
10-3-95
WICHITA, KANSAS

Remarks: Used 65/35 Pozmix 8% gel by Cementers Inc. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

XXXXXXX observe this plugging.

DATE 10-9-95

Signed _____ (TECHNICIAN)

INV. NO. 43703