

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20392-00-01
Spot: NESE Sec/Twnshp/Rge: 16-18S-31W
1924 feet from S Section Line, 635 feet from E Section Line
Lease/Unit Name: REIFSCHNEIDER (OWWO) Well Number: 1
County: SCOTT Total Vertical Depth: 4663 feet

Operator License No.: 31251
Op Name: WABASH ENERGY CORPORATION
Address: PO BOX 595
LAWRENCEVILLE, IL 62439

Production Casing Size: 5.5 feet: 4661 WITH 385 SX CMT
Surface Casing Size: 8.625 feet: 365 WITH 235 SX CMT

\$151⁵⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/30/2003 12:10 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PUMP 41 BBL MUD SPACER TO 2250'. FILL TO SURFACE WITH 260 SX CMT. CHECK BACKSIDE. USE 50 SX CMT IF NECESSARY.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/30/2003 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4517-4522'. CIBP @ 4290'. PERFS AT 4231-4234'. PORT COLLAR @ 2249' WITH 235 SX CMT. PUMP 200# HULLS & 25 SX CMT. PUMP 16 SX GEL & 185 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 250#. PUMP 50 SX CMT DOWN BACKSIDE. MAXIMUM PRESSURE 350#. CMT CAME UP IN CELLAR, SURFACE PIPE HAD A HOLE IN IT.

RECEIVED
JUN 13 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
JUN - 4 2003
KCC Dodge City

Signed Michael J Maier
(TECHNICIAN)

INVOICED
6-13-03
WV. NO. 2003061639

[Handwritten signature]
Form C-2/3