

8-20

To: 1 051196
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,392-0000
App. C NE SE, SEC. 16, T 18 S, R 31 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Operator: Slawson Exploration Company, Inc.
Name & Address 104 South Broadway, Suite 200
Wichita, KS 67202-1165

1980 feet from S section line

640 feet from E section line
Reifschneider "P"

Lease Name Well # 1

County Scott 151.55

Well Total Depth 4663 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 12:30 a.m. Day: 20 Month: 8 Year: 19 89

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2246-64'

1st plug at 2900' with 100 sx cement, 2nd plug at 2264' with 50 sx cement,

3rd plug at 1400' with 80 sx cement, 4th plug at 400' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3 a.m. Day: 20 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2800' with 100 sx cement,

2nd plug at 2264' with 50 sx cement,

3rd plug at 1400' with 80 sx cement,

4th plug at 400' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I () did not observe this plugging.

DATE 8-24-89

INV. NO. 25737
8-20

Signed Richard W. Lacey
(TECHNICIAN)

8-23-89
AUG 23 1989
Richard W. Lacey
Wichita, Kansas