

To: 1-20773
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-31

API NUMBER 15- 171-20,453-0000 1372 R

SE SW NW, SEC. 16, T. 18 S, R. 31 WXE

2970 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Reifschneider Well # 1

Operator: The Dane G. Hansen Trust

County Scott

Name & Address P.O. Box 187

Well Total Depth 4264 138.58 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 224 E. Douglas, Ste. 530, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 31 Month: 1 Year: 1993

Plugging proposal received from Harold Dinkel

(company name) Chief Drilling, Inc. (phone) 316-262-3791

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2294-2315'

1st plug at 2800' with 100 sx cement, 2nd plug at 2320' with 50 sx cement,

3rd plug at 1300' with 50 sx cement, 4th plug at 650' with 50 sx cement,

5th plug at 300' with 50 sx cement, 6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement, 8th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin

Plugging Operations attended by Agent?: All Part

Operations Completed: Hour: 4:15 p.m. Day: 31 Month: 1

ACTUAL PLUGGING REPORT 1st plug at 2800' with 100 sx cement,

2nd plug at 2320' with 50 sx cement, 3rd plug at 1300' with 50 sx cement,

4th plug at 650' with 50 sx cement, 5th plug at 300' with 50 sx cement,

6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement,

8th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

INVOICED

XXXXX/ did not observe this plugging.

DATE: 2-18-93

INV. NO. 27381

Signed Duane Rankin (TECHNICIAN)

STATE RECEIVED
CORPORATION COMMISSION
(TECHNICAL) FEB 22 1993
CONSERVATION DIVISION
WICHITA, KANSAS