

1 060008

11-23

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,396-0000
150' E 88
NE SE, SEC. 17, T 18 S, R 31 W/E

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
S20-670 feet from E section line

Operator License # 3988

Lease Name Morrison "H" Well # 1

Operator: Slawson Exploration Company, Inc.
Name &
Address 104 South Broadway, Suite 200
Wichita, KS 67202-4165

County Scott 148.79

Well Total Depth 4578 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 1 a.m. Day: 23 Month: 11 Year: 19 89

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2266-2285' Elevation 2947' GL

1st plug at 2800' with 100 sx cement, 2nd plug at 2290' with 50 sx cement,

3rd plug at 1420' with 80 sx cement, 4th plug at 410' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 4 a.m. Day: 23 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2800' with 100 sx cement,

2nd plug at 2290' with 50 sx cement,

3rd plug at 1420' with 80 sx cement,

4th plug at 410' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement. 11-29-89

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(XXX did not) observe this plugging.

Signed Case Morris
(TECHNICIAN)

DATE 12-7-89
INV. NO. 26695
11-23