

To: 1 031213
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-9

API NUMBER 15- 171-20,066-0000

562

C SE, SEC. 17, T 18 S, R 31 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8964

Lease Name Lillian Long Well # 1-17

Operator: Reserve Pipeline, Inc.

County Scott 92.00

Name & Address P.O. Box 1274

Well Total Depth 2831 feet

Liberal, KS 67905

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 9 Month: 9 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 2830' w/150 sx cement, PBTD 2796', Perfs at 2740-48, 2763-84'

1st plug sand back to 2700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 2250',

3rd plug pump 80' sx cement at 1600',

4th plug circulate cement from 300' to 0'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 9 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 2700' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 80 sx cement at 1600',

3rd plug pumped 50 sx cement at 864',

4th plug at 290', circulated cement to surface with 70 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 864' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
SEP 15 1992

DATE 10-7-92

Signed Steve Perout (TECHNICIAN)

INV. NO. 36357