

6-9

1 031012

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-171-20,387-0000

NW SE NW, SEC. 11, T 18 S, R 31 W/EX

3640 feet from S section line

3640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name Ramsey "R" Well # 1

Operator: Slawson Exploration Company, Inc.  
Name

County Scott 150.80

Address 104 South Broadway, Suite 200  
Wichita, KS 67202-4165

Well Total Depth 4640 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 381

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 12:30 a.m. Day: 9 Month: 6 Year: 19 89

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2925' KB  
Anhydrite 2259-79'

- 1st plug at 2260' with 50 sx cement, 2nd plug at 1410' with 80 sx cement,
- 3rd plug at 410' with 50 sx cement,
- 4th plug at 40-0' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:15 a.m. Day: 9 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2260' with 50 sx cement,

2nd plug at 1410' with 80 sx cement,

3rd plug at 410' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

6-13-89  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** (do not) observe this plugging.

DATE 6-14-89

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 25068