

To: 1 051404  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-21

249

API NUMBER 15-171-20,130-0000  
C NE, SEC. 10, T 18 S, R 31 WAE

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3857

Lease Name Huling Well # 1-10

Operator: Unico Inc.

County Scott 94.57

Name & Address P.O. Box 35

Well Total Depth 2910 feet

Farmington, NM 87499

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 20 Month: 2 Year: 19 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service (phone) 316-675-8349

were: 4 1/2" at 2909' w/150 sx cement, PRTD 2880', Perfs at 2756-2760'

1st plug pump 20 sx cement and 2 sx hulls on bottom,, 2nd plug pump 50 sx cement at

1600', 3rd plug pump 50 sx cement at 920', 4th plug pump 50 sx cement at 390',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 2 p.m. Day: 21 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 1/2 sx hulls and 20 sx cement to 2600',

2nd plug shot pipe at 1566', pumped 50 sx cement down 4 1/2" to 1500',

3rd plug pumped through casing at 920' with 50 sx cement,

4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement.

Remarks: Used common cement by Midwest. Recovered 955' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(did / ~~did not~~) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

INVOICED

FEB 26 1991  
2-26-91

DATE 3-5-91

INV. NO. 31008