

1080204
TO:

7-1

API NUMBER 15-171-20,532-0000

STATE CORPORATION COMMISSION

NW-SE SEC. 6, T 18 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION

1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BERNING WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT

OPERATOR LICENSE # 31251

WELL TOTAL DEPTH 4673' 151.88 FEET

OPERATOR: WABASH ENERGY CORPORATION

CONDUCTOR PIPE: SIZE " FEET

NAME AND P.O. BOX 595

SURFACE CASING: SIZE 8 5/8" FEET 222'

ADDRESS LAWRENCEVILLE, IL 62439

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC. LICENSE NUMBER 31548

ADDRESS P.O. BOX 763 HAYS KS 67601

COMPANY TO PLUG AT: HOUR: 1:15 PM DAY: 1 MONTH: JULY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM TOM ALM

(COMPANY NAME) DISCOVERY DRILLING, INC. (PHONE) 785-623-2920

WERE: TO FILL HOLE WITH HEAVY MUD AND SPOT CEMENT THROUGH DRILL PIPE

1ST PLUG AT 2300' WITH 50 SX CEMENT, 2ND PLUG AT 1500' WITH 50 SX CEMENT,

3RD PLUG AT 750 WITH 40 SX CEMENT, 4TH PLUG AT 250' W/40 SX CMT, 5TH PLUG AT 40' W/10 SX

CIRCULATE RAT HOLE WITH 15 SX OF CEMENT. CIRCULATE MOUSEHOLE WITH 10 SX OF CEMENT

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00PM DAY: 1 MONTH: JULY YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG AT 2300' WITH 50 SX CEMENT,

2ND PLUG AT 1500' WITH 50 SX CEMENT, 3RD PLUG AT 750' WITH 40 SX CEMENT,

4TH PLUG AT 250' WITH 40 SX CEMENT, 5TH PLUG AT 40' WITH 10 SX CEMENT,

CIRCULATE RATHOLE WITH 15 SX OF CEMENT

CIRCULATE MOUSEHOLE WITH 10 SX OF CEMENT

JUL 10 1998
7-10-98
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLOW SEAL, CEMENTED BY ALLIED CEMENTING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DAD) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube
(TECHNICIAN) FORM CP-2/3

INVOICED
DATE JUL 13 1998
INV. NO. 50909