

To: 1 090002
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-27 332
API NUMBER 15-171-20,412-0000
C SE, SEC. 5, T 18 S, R 31 W/E
1320 feet from S section line
1330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name Ross "H" Well # 1

Operator: Slawson Exploration Company, Inc.
Name & Address: 104 S. Broadway, Suite 200
Wichita, KS 67202-4165

County Scott 75.72
Well Total Depth 2330 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 8 p.m. Day: 27 Month: 8 Year: 19 90

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2290-2308'
1st plug at 2300' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,
3rd plug at 750' with 50 sx cement, 4th plug at 370' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10 p.m. Day: 27 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement,
2nd plug at 1500' with 80 sx cement,
3rd plug at 750' with 50 sx cement,
4th plug at 370' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE: 9-17-90
INV. NO. 29312

Signed [Signature] (TECHNICIAN)

RECEIVED
SEP 16 1990
CONSERVATION DIVISION
WICHITA, KANSAS