

To: 1-120384  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-13  
API NUMBER 15- 171-20,407-0000 132 P

App. SE SW, SEC. 5, T 18 S, R 31 (W/R)  
321-90 670 feet from S section line

TECHNICIAN'S PLUGGING REPORT

3350 feet from E section line

Operator License # 3988

Lease Name Pfenninger "D" Well # 1

Operator: Slawson Exploration Company, Inc.  
Name & Address 104 South Broadway, Suite 200  
Wichita, KS 67202-4165

County Scott 75.99

Well Total Depth 2338 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2 a.m. Day: 13 Month: 3 Year: 19 90

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2302'  
1st plug at 2300' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,  
3rd plug at 400' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 5:30 a.m. Day: 13 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement,  
2nd plug at 1400' with 80 sx cement,  
3rd plug at 400' with 40 sx cement,  
4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED

(additional description is necessary, use BACK of this form.)

DATE 3-28-90 I (XXXX) did not observe this plugging.

INV. NO. 27755  
3-13

Signed Duane Rankin (TECHNICIAN)