

TO: 1090903

3-4

API NUMBER 15- 171-20,522 -0000

STATE CORPORATION COMMISSION

NW NE SW , SEC. 18 , T 18 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WEISENBERGER WELL # 1-18

TECHNICIAN'S PLUGGING REPORT COUNTY SCOTT

OPERATOR LICENSE # 4243 WELL TOTAL DEPTH 4630 150.48 FEET

OPERATOR: CROSS BAR PETROLEUM, INC. PRODUCTION CSG: SIZE FEET

NAME AND 7570 W. 21ST BLDG 1014 SUITE B SURFACE CASING: SIZE 8 5/8 FEET 313

ADDRESS WICHITA, KS 67205

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR LD DRILLING LICENSE NUMBER 6039

ADDRESS RR1, BOX 183-B GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 2:30 AM DAY: 4 MONTH: 3 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM NORM

(COMPANY NAME) LD DRILLING (PHONE) 316-793-3051

WERE: TO FILL HOLE WITH HEAVY MUD AND SPOT CEMENT THROUGH PIPE

1ST PLUG AT 2310 WITH 50 SX CEMENT, 2ND PLUG AT 1500 WITH 80 SX CEMENT,

3RD PLUG AT 750 WITH 50 CEMENT, 4TH PLUG 330 WITH 50SX, 5TH PLUG 40 WITH 10SX 6TH PLUG

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 6:30 AM DAY: 4 MONTH: 3 YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG AT 2310 WITH 50 SX CEMENT,

2ND PLUG AT 1500 WITH 80 SX CEMENT,

3RD PLUG AT 750 WITH 40 SX CEMENT'

4TH PLUG AT 330 WITH 50SX CEMENT

5TH PLUG AT 40 WITH 10 SX CEMENT

6TH PLUG CIRCULATE RAT HOLE WITH 15SX CEMENT

REMARKS: USED 60/40 6% GEL WITH 1/4 LB FLO SEAL BY ALLIED CEMENTING
IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) NOT OBSERVE THIS PLUGGING.
DATE 3-10-98

SIGNED [Signature]
(TECHNICIAN) FORM CP-2/3

INV. NO. 50185
3-4

86-6-11
3-10-98
316-793-3051

[Handwritten mark]