

1080311

TO: STATE CORPORATION COMMISSION

API NUMBER 15-171-20,439-0002
C N/2 NW SW SEC. 18, T 18 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4710 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WEISENBERGER WELL # 1-18 OWWO

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT

149,83

OPERATOR LICENSE # 5011

WELL TOTAL DEPTH 4610 FEET

OPERATOR: VIKING RESOURCES, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 4411' WITH 225 SX

NAME AND ADDRESS 105 S BROADWAY, SUITE 1040 WICHITA, KS 67202

SURFACE CASING: SIZE 8 5/8" @ 270' WITH SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR WHITETAIL CRUDE, INC. LICENSE NUMBER 31627

ADDRESS PO BOX 544 NESS CITY, KS 67560-0544

COMPANY TO PLUG AT: HOUR: 2:45 PM DAY: 24 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM SHAWN DEVLIN

(COMPANY NAME) WHITETAIL CRUDE, INC. (PHONE) 785-798-3641

WERE: PERFS AT 4014-18. DV TOOL @ 2250' WITH 400 SX CEMENT.

PUMPED DOWN 4 1/2" WITH 25 SX CEMENT AND 300# HULLS, 9 SX GEL, 115 SX CEMENT. MAXIMUM PRESSURE

400#. SHUT IN ON VACUUM. CHECKED CEMENT TOP ON 05/25/00. CEMENT TOP AT 350'. TOPPED

OFF WITH 25 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:45 PM DAY: 24 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED DOWN 4 1/2" WITH 25 SX CEMENT AND 300# HULLS, 9 SX GEL, 115 SX CEMENT. MAXIMUM PRESSURE

400#. SHUT IN ON VACUUM. CHECKED CEMENT TOP ON 05/25/00. CEMENT TOP AT 350'. TOPPED

OFF WITH 25 SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION

JUN 8 2000

6-8-00

REMARKS: USED 65/35 POZMIX 8% GEL BY SWIFTS. NO CASING RECOVERED.
(IF ADDITIONAL DISCUSSION IS NECESSARY, USE BACK OF THIS FORM.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

I (DID) OBSERVE THIS PLUGGING.

DATE 6/9/00 SIGNED

Kevin D. Strube (TECHNICIAN)

FORM CP-2/3

INV. NO. 61858

