

1 051954 8-23

API NUMBER 15- 171-20,439-0000 ⁰¹

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

N/2 NW SW, SEC. 18, T 18 S, R 31 W/E

2310 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Weisenberger Well # 1-18

Operator: Chief Drilling, Inc./Brito Oil Co., Inc

County Scott 149.83

Name & Address 120 S. Market, Ste. 300

Well Total Depth 4610 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Company License Number _____

Address P.O. Box 31, Russell, KS 67665

Company to plug at: Hour: 10 a.m. Day: 23 Month: 8 Year: 1995

Plugging proposal received from Gary Lindenmuth

(company name) Chief Drilling, Inc. (phone) 316-262-3791

were: 4 1/2" at 4020' w/225 sx cement, PBD 4411', Perfs at 4286-92, 4302-06, 3960-63'

DV at 2250' w/400 sx cement

1st plug pump 200 lbs. hulls and 235 sx cement down 4 1/2" casing,

2nd plug pump 15 sx cement down 8 5/8" X 4 1/2" annulus.

8-28-95
AUG 28 1995

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 23 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 235 sx cement down 4 1/2" casing.

Maximum pressure 1000 psi and shut in 750 psi.

2nd plug pumped 15 sx cement down 8 5/8" X 4 1/2" annulus.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE SEP 01 1995

INV. NO. 43397

Signed Richard M. Lacey (TECHNICIAN)