

To: 1 070039
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

185-10112-0001
API NUMBER 15- ~~Drilled 3/75, reentered 1961~~
C NE SE, SEC. 16, T 25 S, R 15 W/E
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers Inc. of Kansas
Name & Address: P.O. Box 8647
Wichita, KS 67208

Lease Name Curtis B OWWO Well # 1
County Stafford 140.08
Well Total Depth 4310 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10:45 a.m. Day: 7 Month: 11 Year: 1997

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

work: 4 1/2" at 4306' w/100 sx cement, PBSD 4275', Perfs at 4234-44'
1st plug sand back to 4180' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by ^{DEWS} Scott Alberg
(TECHNICIAN) 11-13-97

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 a.m. Day: 7 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4180' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement; 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 175 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 11-17-97

Signed 
(TECHNICIAN)

INV. NO. 49511