

To: 1 090809 5-8  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 101-21,735-0000  
C SW NW, SEC. 2, T 16 S, R 30 W/E  
1980 feet from N section line  
660 feet from W section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name & Address: P.O. Box 48788  
Wichita, KS 67201-8788

Lease Name York Well # 1  
County Lane 141.38  
Well Total Depth 4350 feet  
Conductor Pipe: Size          feet  
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well          Gas Well          Input Well          SMD Well          O&A X  
Other well as hereinafter indicated         

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606  
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 8 Month: 5 Year: 19 97

Plugging proposal received from Ed McKenna  
(company name) Murfin Drilling Company, Inc. (phone) 316-267-3241

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2051'  
1st plug at 2050' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,  
3rd plug at 650' with 40 sx cement, 4th plug at 300' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All          Part          None X

Operations Completed: Hour: 5:30 a.m. Day: 8 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2050' with 50 sx cement,  
2nd plug at 1200' with 80 sx cement, 3rd plug at 650' with 40 sx cement,  
4th plug at 300' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
did not observe this plugging.  
DATE MAY 14 1997  
INV. NO. 48115  
5-8 JUL 11 1997

Signed [Signature]  
(TECHNICIAN)

5-13-97