

1050306

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,019-0000

NE SW NE, SEC. 2 ; T 16 S, R 30 W/8
N SE Corner of
3610 feet from ~~XXX~~ section line
W SE Corner of
1680 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name York 'II' Well # 3

Operator: Donald C. Slawson
Name & Address 200 Douglas Building
Wichita, KS 67202

County Lane

Well Total Depth 4415 feet *143.49*

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 387

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 4 Month: August Year: 19 84

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2100' with 50 sx cement

2nd plug at 1100' with 50 sx cement

3rd plug at 700' with 40 sx cement

4th plug at 420' with 40 sx cement

solid bridge Plugging Proposal Received by *Richard W. Lacey*
5th plug hulls - plug at 40' -- cement to surface with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 15 sx cement
Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 pm Day: 4 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1100' with 50 sx

cement, 3rd plug at 700' with 40 sx cement, 4th plug at 420' with 40 sx cement, 5th & 6th

plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED
(xxx) / do not observe this plugging.

DATE 8-17-84

Signed *Richard W. Lacey*
(TECHNICIAN)

INV. NO. 3230

SEP 11 1984

FORM CP-2/3
Rev. 01-8

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1984
8-16-84
CONSERVATION DIVISION
Wichita, Kansas