

To: 1 050705
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE NW NE App; SEC. 7, T 16 S, R 16
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,334-0006 *R*
4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4525
Operator: A. Francis Vonfeldt Co.
Name & Address: P. O. Box 357, 505 S. Colorado
Plainville, KS 67663

Lease Name Dome Well # 1
County Rush 116.03
Well Total Depth 3570 Arbuckle feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1012

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Western Kansas Drilling, Inc. License Number 4083
Address P. O. Box 126, 1111 East 30th, Hays, KS 67601

Company to plug at: Hour: 4:00 pm Day: 25 Month: November Year: 19 85

Plugging proposal received from Frank Tagart
(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1930.5 GL
Anhydrite 1050

- 1st plug in the Arbuckle with 50 sx cement if 50' or more
- 2nd plug 30' below the surface pipe with 50 sx cement
- 3rd plug at 700' with 40 sx cement solid bridge
- 4th plug hulls- plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 pm Day: 25 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3526' with 50 sx cement, 2nd plug at 1050' with 50
sx cement, 3rd plug at 700' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 11 1985
INV. NO. 11468
11-25

DEC 5 1985 Signed Richard W. Lacey
(TECHNICIAN)

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 11 15 85 month day year

API Number 15-165-21,334-0000

OPERATOR: License # 4525 App. Name A. Francis Vonfeldt Co. Address Box 357, 505 S. Colo. City/State/Zip Plainville, KS 67663 Contact Person A. Francis Vonfeldt Phone (913) 434-2408

NE NW NE Sec. 7 Twp. 16 S. Rg. 16 East 4950 Ft. from South Line of Section 1650 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 4574 4083 Name Western Kansas Drilling, Inc. City/State 1111 S. 30th, Box 126, Hays, KS 67301 Well Drilled For: Well Class: Type Equipment: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet County Rush Co Lease Name Dome Well # 1 Ground surface elevation feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 100 Depth to bottom of usable water 660 Surface pipe planned to be set 1000 Projected Total Depth 3550 feet Formation Arbuckle-K.C.

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 11/8/85 Signature of Operator or Agent Title as agent

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 1 2 This Authorization Expires 5-8-86 Approved By 11-8-85

set 1000 of 8 3/8 on 11/14/85

USHER Frank Tognatt 3570 FORMATION 1558 SURFACE PIPE 1050 ELEVATION 1980.5 G.L. ANHYDRITE 1050 ELEVATION STARTING TIME & DATE COMPLETION TIME & DATE 600 PM 11/25/85 1st PLUG @ Arbuckle FT. W/ 50 SX ARBUCKLE 2nd PLUG @ 30' SURFACE FT. W/ 50 SX 3rd PLUG @ 700 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 50 FT/SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 100 SX WATER WELL PLUGGED W/ None SX CEMENT COMPANY Sund TECHNICIAN James Propp

STATE CORPORATION COMMISSION

DEC 5 1985

CONSERVATION DIVISION