

1010148

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,192-0000 *R*
SE NW SE, SEC. 17, T 16 S, R 16 W/X

1650 feet from ~~NYS~~ section line
1560 feet from ~~XYE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Dome "A" Well # 1

Operator: Thunderbird Drilling, Inc.

County Rush

Name & Address P. O. Box 18407

Well Total Depth 3550 feet

Wichita, KS 67218

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131

Address P. O. Box 18407, Wichita, KS 67218

Company to plug at: Hour: 6:45 pm Day: 27 Month: June Year: 19 84

Plugging proposal received from Lawrence Herman

(company name) Thunderbird (phone) 913-726-3363

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1085' with 50 sx cement

2nd plug at 625' with 50 sx cement

3rd plug at 332' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Ker Breaker
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8:00 pm Day: 27 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1085' with 50 sx cement, 2nd plug at 625' with 50
sx cement, 3rd plug at 332' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

STATE CORPORATION COMMISSION

JUL 06 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied # 37294
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

Signed Ker Breaker
(TECHNICIAN)

DATE 7-16-84

INV. NO. 2528

JUL 17 1984